


LOCATION PLAN SCALE: $1" = 2.000' \pm$

WILDLIFE PROTECTION NOTES (ENV-WQ 1504.17)

- ALL OBSERVATIONS OF THREATENED OR ENDANGERED SPECIES SHALL BE REPORTED IMMEDIATELY TO THE NEW HAMPSHIRE FISH AND GAME DEPARTMENT NONGAME AND ENDANGERED WILDLIFE ENVIRONMENTAL REVIEW PROGRAM BY PHONE AT 603-271-2461 AND BY EMAIL AT NHFGREVIEW@WILDLIFE.NH.GOV. EMAIL SUBJECT LINE: NHB24-0767, JENNESSTOWN MANOR, WILDLIFE SPECIES OBSERVATION.
 PHOTOGRAPHS OF THE OBSERVED SPECIES AND NEARBY ELEMENTS OF HABITAT OR AREAS OF LANI
- DISTURBANCE SHALL BE PROVIDED TO NHF&G IN DIGITAL FORMAT FOR VERIFICATION AS FEASIBLE; IN THE EVENT A THREATENED OR ENDANGERED SPECIES IS OBSERVED ON THE PROJECT SITE DURING THE TERM OF THE PERMIT, THE SPECIES SHALL NOT BE DISTURBED, HANDLED, OR HARMED IN ANY WAY PRIOR TO CONSULTATION WITH NHF&G AND IMPLEMENTATION OF CORRECTIVE ACTIONS RECOMMENDED BY NHF&G, IF ANY TO ASSURE THE PROJECT DOES NOT APPRECIABLY JEOPARDIZE THE CONTINUED EXISTENCE OF THREATENED AND ENDANGERED SPECIES AS DEFINED IN FIS 1002.04
- THE NHF&G, INCLUDING ITS EMPLOYEES AND AUTHORIZED AGENTS, SHALL HAVE ACCESS TO THE PROPERT


RESIDENTIAL SITE PLAN JENNESSTOWN MANOR MAP 7; LOTS 39 & 39-1 ROUTE 103 WARNER, NEW HAMPSHIRE





LEDGE AND ROCK REMOVAL

PEACOCK HILL ROAD, LLC CERTIFIES THAT THE INTENT IS THAT ALL LEDGE AND ROCK REMOVAL WILL BE CONDUCTED BY MECHANICAL MEANS. SHOULD SITE CONDITIONS DETERMINE BLASTING OF LESS THAN 5,000 CY IS REQUIRED, PEACOCK HILL ROAD, LLC CERTIFIES BLASTING BEST MANAGEMENT PRACTICES OUTLINED IN ENV-WQ 1510 WILL BE FOLLOWED. NO BLASTING IN EXCESS OF 5,000 CY IS PERMITTED WITHOUT CONTACTING THE DESIGN ENGINEER AND NHDES ALTERATION OF TERRAIN.




OWNER/APPLICANT: PEACOCK HILL ROAD, LLC 145 OLD TOWN ROAD WEARE, NH 03281

ENGINEER:

KEACH-NORDSTROM ASSOCIATES, INC. 10 COMMERCE PARK NORTH, SUITE 3B BEDFORD, NEW HAMPSHIRE 03110 (603) 627-2881

SURVEYOR:


J.E. BELANGER LAND SURVEYING PLLC 61 OLD HOPKINTON ROAD DUNBARTON, NEW HAMPSHIRE 03046 (603) 774-3601








MARCH 25, 2024 REVISED NOVEMBER 18, 2025 PROJECT NO. 24-0307-1

SHEET TITLE SHEET No. EXISTING CONDITIONS PLAN SITE PLAN EASEMENT PLAN GRADING, DRAINAGE & UTILITY PLAN EROSION CONTROL PLAN LANDSCAPE PLAN LIGHTING PLAN SITE VISIBILITY FROM ROAD PLAN & PROFILE SIGHT DISTANCE PLAN DRIVEWAY PROFILE PLAN CONSTRUCTION DETAILS 12 - 16ARCHITECTURAL DRAWINGS A1 - A5









NOTES:

1. THE PURPOSE OF THIS PLAN IS TO DEPICT THE PROPOSED EASEMENTS ON ASSESSOR'S MAP 7 LOTS 39 AND 39-1,

2. REFERENCE THESE PARCELS AS LOT 39 ON WARNER TAX MAP 7.

ACCESS AND MAINTENANCE EASEMENT — ON MAP 7 LOT 39 TO BENEFIT MAP 7 LOT 39—1
ACCESS AND MAINTENANCE EASEMENT — ON MAP 7 LOT 39—1 TO BENEFIT MAP 7 LOT 39
DRAINAGE EASEMENT — GENERAL DRAINAGE EASEMENT ON MAP 7 LOTS 39 AND 39—1 FOR MUTUAL BENEFIT



LEGEND

☐ GB-F GRANITE BOUND FOUND

■ SB-F STONE BOUND FOUND

- ABUTTER LINE

--- SETBACK


--- EASEMENT

--- --- WETLAND BUFFER

REFERENCE PLANS:

 PLAN ENTITLED "BOUNDARY PLAN PREPARED FOR MURIEL I. LEGER", SCALE: 1"=100', DATED FEB. 14, 1991. PREPARED BY RICHARD D. BARTLETT & ASSCCIATES, INC. AND RECORDED AT M.C.R.D. ON JUNE 26, 1991 AS PLAN NO. 12109.

- 2. PLAN ENTITLED "SUBDIVISION PLAN PROPERTY OF THEODORE & ELIZABETH YOUNG LOCATED IN WARNER, NEW HAMPSHIRE" SCALE: 1"=100', DATED FEBRUARY 1988. PREPARED BY JEFFREY A. EVANS AND RECORDED AT M.C.R.D. ON JUNE 7, 1988 AS PLAN NO. 10385.
- 3. PLAN PREPARED BY B.F. HOWARD ASSOCIATES, FOR GILBERT J. TEDSTONE, SCALE: 1"=100', DATED 8/29/77. RECORDED AT M.C.R.D. ON NOVEMBER 14, 1977 AS PLAN NO. 5047.
- 4. STATE OF NEW HAMPSHIRE R.O.R. PLANS PROJECT NO. F243(8) FISCAL YEAR 1953, SHEETS 10 THRU
- 5. "SUBDIVISION PLAN JENESSTOWN MANOR MAP 7 LOT 39 PREPARED FOR PEACOCK HILL ROAD, LLC", SCALE: 1"=100', DATED MARCH 25, 2025. PREPARED BY KEACH-NORDSTROM ASSOCIATES, INC.



EASEMENT PLAN

JENNESSTOWN MANOR MAP 7, LOTS 39 & 39-1

ROUTE 103 WARNER, NEW HAMPSHIRE MERRIMACK COUNTY

OWNER/APPLICANT:

PEACOCK HILL ROAD, LLC 145 OLD TOWN ROAD WEARE, NH 03281 BK. 3829 PG. 2512




KEACH-NORDSTROM ASSOCIATES, INC.


Civil Engineering Land Surveying Landscape Architecture 10 Commerce Park North, Suite 3B, Bedford, NH 03110 Phone (603) 627-2881



		REVISIONS	
No.	DATE	DESCRIPTION	BY
1	5/22/25	PER PB AND AOT COMMENTS	AEW
2	9/4/25	PER AOT COMMENTS	AEW
3	10/2/25	PER AOT COMMENTS	AEW
4	10/31/25	PER ARIES & FIRE COMMENTS	JDL
5	11/18/25	PER AOT & COND. OF APPROVAL	AEW
DATI	E: MARCH 2	5. 2025 SCALE: 1" = 40'	-2-270

PROJECT NO: 24-0307-1 SHEET 4 OF 16





SITE SPECIFIC SOIL MAP UNIT KEY

SYMBOL	MAP UNIT	HISS SYM	HSG	
55	HERMON VERY STONY	121	В	
442	CHICHESTER	221	В	1 7
58	WAUMBEK	321	A	
829	WAUMBEK-HERMON ASSOCIATION	321	В	- 1
414	MOOSILAUKE POORLY DRAINED	521	C	145
399	LEDGE OUTCROP	228	D	

THIS MAP PRODUCT IS WITHIN THE TECHNICAL STANDARDS OF THE NATIONAL COOPERATIVE SOIL SURVEY. IT IS A SPECIAL PURPOSE PRODUCT, INTENDED FOR INFILTRATION REQUIREMENTS BY THE NH DES ALTERATION OF TERRAIN BUREAU. IT WAS PRODUCED BY A PROFESSIONAL SOIL SCIENTIST, AND IS NOT A PRODUCT OF THE USDA NATURAL RESOURCES CONSERVATION SERVICE THERE IS A REPORT THAT ACCOMPANIES THIS MAP.

THE SITE SPECIFIC SOIL SURVEY (SSSS) WAS PRODUCED NOVEMBER 23, 2024 AND WAS PREPARED BY LUKE HURLEY, CSS # 095, HURLEY ENVIRONMENTAL AND LAND PLANNING, LLC. SOILS WERE IDENTIFIED WITH THE NEW HAMPSHIRE STATE—WIDE NUMERICAL SOILS LEGEND, USDA NRCS, DURHAM, NH. ISSUE # 10, JANUARY 2011. THE NUMERIC LEGEND WAS AMENDED TO IDENTIFY THE CORRECT SOIL COMPONENTS OF THE COMPLEX.

HYDROLOGIC SOIL GROUP FROM KSAT VALUES FOR NEW HAMPSHIRE SOILS, SOCIETY OF SOIL SCIENTISTS OF NEW ENGLAND, SPECIAL PUBLICATION NO. 5, SEPTEMBER, 2009.



LOAM & SEED ALL DISTURBED AREAS (TYP.)

CONSTRUCTION NOTES:

 THE PURPOSE OF THIS PLAN IS TO SHOW THE PROPOSED GRADING, DRAINAGE AND UTILITY SYSTEMS FOR THIS SITE.

- 2. ALL WORK SHALL CONFORM TO THE APPLICABLE REGULATIONS AND STANDARDS OF THE TOWN OF WARNER, AND SHALL BE BUILT IN A WORKMANLIKE MANNER IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS. THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, STATE OF NEW HAMPSHIRE, DEPARTMENT OF TRANSPORTATION, APPROVED AND ADOPTED 2016 ARE HEREBY INCORPORATED BY REFERENCE.
- . ALL STUMPS, ROOTS, BRANCHES, BRUSH, WOODS AND OTHER PERISHABLE MATERIAL RESULTING FROM THE CLEARING AND GRUBBING OPERATIONS SHALL BE DISPOSED OF BY AN APPROVED METHOD.
- 4. DEBRIS REMOVED FROM THE SITE SHALL BE DISPOSED OF IN ACCORDANCE WITH ALL LOCAL, STATE AND FEDERAL REGULATIONS.
- 5. PARKING LOT CONSTRUCTION SHALL CONFORM TO THE TYPICAL SECTIONS AND DETAILS SHOWN ON THE PLANS, AND SHALL MEET THE REQUIREMENTS.
- ALL DISTURBED AREAS SHALL BE LOAMED AND SEEDED.
 SEE DETAILS FOR DRAINAGE SPECIFICATIONS.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING AND DETERMINING THE LOCATION, SIZE AND ELEVATION OF ALL EXISTING UTILITIES, SHOWN OR NOT SHOWN ON THESE PLANS, PRIOR TO THE START OF ANY CONSTRUCTION THE ENGINEER SHALL BE NOTIFIED IN WRITING OF ANY UTILITIES FOUND INTERFERING WITH THE PROPOSED CONSTRUCTION, AND APPROPRIATE REMEDIAL ACTION TAKEN BEFORE PROCEEDING WITH THE WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING
- "DIG SAFE" AT 811 AT LEAST 72 HOURS BEFORE DIGGING.
 9. NO TEST BORINGS WERE COMPLETED OR PROVIDED.


GRADING, DRAINAGE, & UTILITIES PLAN

JENNESSTOWN MANOR MAP 7, LOTS 39 & 39-1

> ROUTE 103 WARNER, NEW HAMPSHIRE MERRIMACK COUNTY

> > OWNER/APPLICANT:

PEACOCK HILL ROAD, LLC 145 OLD TOWN ROAD WEARE, NH 03281 BK. 3829 PG. 2512





Civil Engineering Land Surveying Landscape Architecture 10 Commerce Park North, Suite 3B, Bedford, NH 03110 Phone (603) 627-2881

			RE
OF STEVEN STEVEN	No.	DATE	
STEVEN B.	1	5/22/25	PER PB A
STEVEN	2		PER AOT
B. WEACH	3	10/2/25	PER AOT
7659	4	10/31/25	PER ARIES
The state of the s	5	11/18/25	PER AOT
MALDON	DATI	E: MARCH 2	5, 2025
	PRO.	JECT NO: 2	4-0307-1

		REVISION	S	
No.	DATE	DESC	RIPTION	BY
1	5/22/25	PER PB AND AO	T COMMENTS	AEW
2	9/4/25	PER AOT COMME	NTS	AEW
3		PER AOT COMME		AEW
4	10/31/25	PER ARIES & FIR	E COMMENTS	JDL
5	11/18/25	PER AOT & COND). OF APPROVAL	AEW
De La	Landy II		ell I de la la	100
DATI	E: MARCH 2	5, 2025	SCALE: $1" = 40'$	


SHEET 5 OF 16





--- EDGE OF PAVEMENT IRON ROD FOUND ---- EDGE OF GRAVEL RAILROAD FOUND DRILL HOLE FOUND _____ 2' CONTOUR BENCHMARK STONEWALL UTILITY POLE · · · · · · · · · SOIL LINE SPOT LIGHT ____ - ___ SETBACK ___ - - _ _ EASEMENT WELL DOUBLE CATCH BASIN RIP-RAP FLARED END SECTION ABUTTER LINE PROPERTY LINE DRAINAGE LINE . TREELINE

> LOAM & SEED ALL DISTURBED AREAS (TYP.)



EROSION CONTROL NOTES:

THE PURPOSE OF THIS PLAN IS TO DEPICT THE REQUIRED ONSITE TEMPORARY CONSTRUCTION EROSION CONTROL MEASURES AS WELL AS THE PERMANENT EROSION CONTROL MEASURES.

2. ALL MEASURES IN THE PLAN SHALL MEET AS A MINIMUM THE BEST MANAGEMENT PRACTICES SET FORTH IN VOLUME 3 OF THE NEW HAMPSHIRE STORMWATER MANUEL TITLED "EROSION AND SEDIMENT CONTROLS DURING CONSTRUCTION," DATED DECEMBER 2010, AS AMENDED FROM TIME TO TIME.

3. WHENEVER PRACTICAL, NATURAL VEGETATION SHALL BE RETAINED, PROTECTED OR SUPPLEMENTED. THE STRIPPING OF VEGETATION SHALL BE DONE IN A MANNER THAT MINIMIZES SOIL EROSION.

4. APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO LAND DISTURBANCE USING WILDLIFE FRIENDLY EROSION CONTROL MATERIALS TO PREVENT TRAPPING OF

5. THE AREA OF DISTURBANCE SHALL BE KEPT TO A MINIMUM. DISTURBED AREAS REMAINING IDLE FOR MORE THAN 5 DAYS SHALL BE STABILIZED. . MEASURES SHALL BE TAKEN TO CONTROL EROSION WITHIN THE PROJECT AREA. SEDIMENT IN RUNOFF WATER SHALL BE TRAPPED AND RETAINED WITHIN THE PROJECT AREA USING APPROVED MEASURES.

WETLAND AREAS AND SURFACE WATERS SHALL BE PROTECTED FROM SEDIMENT. 7. OFFSITE SURFACE WATER AND RUNOFF FROM UNDISTURBED AREAS SHALL BE DIVERTED AWAY FROM DISTURBED AREAS WHERE FEASIBLE OR CARRIED NON-EROSIVELY THROUGH THE PROJECT AREA.

INTEGRITY OF DOWNSTREAM DRAINAGE SYSTEMS SHALL BE MAINTAINED. 8. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED IN FUNCTIONING

CONDITION UNTIL FINAL SITE STABILIZATION IS ACCOMPLISHED. 9. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED AFTER FINAL SITE STABILIZATION. TRAPPED SEDIMENT AND OTHER DISTURBED SOIL AREAS RESULTING FROM THE REMOVAL OF TEMPORARY MEASURES SHALL BE PERMANENTLY STABILIZED WITHIN 5 DAYS UNLESS

CONDITIONS DICTATE OTHERWISE. CONDITIONS DICTATE OTHERWISE.

10. THE TOWN OF WARNER SHALL RESERVE THE RIGHT TO REQUIRE FURTHER EROSION CONTROL PRACTICES DURING CONSTRUCTION SHOULD THEY FIND IT NECESSARY.

11. SNOW ACCUMULATED DURING THE WINTER CONSTRUCTION CONDITIONS SHOULD BE STORED IN THE STAGING & STOCKPILE AREA DETERMINED BY THE CONTRACTOR, SURROUNDED BY SILT FENCE.

12. THE CONTRACTOR SHALL NOT DISCHARGE RUNOFF FROM UNSTABILIZED AREAS OF THE SITE TO

INFILTRATION BMPS.

13. PERIODIC INSPECTION AND MAINTENANCE OF THE CULVERTS AND CATCH BASINS SHALL OCCUR. SEE OPERATIONS AND MAINTENANCE PLAN FOR DETAILS.


EROSION CONTROL PLAN

JENNESSTOWN MANOR MAP 7, LOTS 39 & 39-1

> ROUTE 103 WARNER, NEW HAMPSHIRE MERRIMACK COUNTY

> > OWNER/APPLICANT:


PEACOCK HILL ROAD, LLC 145 OLD TOWN ROAD WEARE, NH 03281 BK. 3829 PG. 2512



Civil Engineering Land Surveying Landscape Architecture 10 Commerce Park North, Suite 3B, Bedford, NH 03110 Phone (603) 627-2881

OF NEW HAMBURE	No.
OF MAMANY	110.
STEVEN E	12.12
/ A B. \\==	2
MEACH ME	3
No. 7659 0 =	4
Man of His	5
A TONGE OF THE PARTY OF THE PAR	
MININININI WALL	DA
1.	PR

		REVISIO	NS	
No.	DATE	DES	CRIPTION	BY
1	5/22/25	PER PB AND AC	OT COMMENTS	AEW
2	9/4/25	PER AOT COMM	ENTS	AEW
3		PER AOT COMM		AEW
4	10/31/25	PER ARIES & FI	RE COMMENTS	JDL
5	11/18/25	PER AOT & CON	ID. OF APPROVAL	AEW
DAT	E: MARCH 2	5, 2025	SCALE: 1" = 40'	
PRO	JECT NO: 2	4-0307-1	SHEET 6 OF 16	3



UTILITY NOTE

THE UNDERGROUND UTILITIES DEPICTED HEREON HAVE BEEN DRAWN FROM FIELD SURVEY INFORMATION AND OR PLOTTED FROM EXISTING DRAWINGS. KEACH-NORDSTROM ASSOCIATES, INC. MAKES NO GUARANTEES THAT THE UNDERGROUND UTILITIES DEPICTED COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. FURTHER, KEACH—NORDSTROM ASSOCIATES, INC. DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM THE INFORMATION AVAILABLE. KEACH—NORDSTROM ASSOCIATES, INC. HAS NOT PHYSICALLY LOCATED THE UNDERGROUND PORTIONS OF THE UTILITIES.

NPDES NOTE

THIS PROJECT DISTURBS IN EXCESS OF 1-ACRE OF LAND.
THEREFORE IT WILL BE REQUIRED TO OBTAIN NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT COVERAGE AS ISSUED BY THE ENVIRONMENTAL PROTECTION AGENCY (EPA). THE OWNER/DEVELOPER AND "OPERATOR" (GENERAL CONTRACTOR) SHALL EACH BE REQUIRED TO PREPARE AND SUBMIT A NOTICE OF INTENT (NOI) TO THE EPA PRIOR TO THE START OF CONSTRUCTION AND SHALL BE RESPONSIBLE FOR THE PREPARATION AND IMPLEMENTATION OF A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) MEETING THE REQUIREMENTS OF THE CURRENT CONSTRUCTION GENERAL PERMIT.



BENCHMARK UTILITY POLE

CATCH BASIN PROPOSED CATCH BASIN PROPOSED OUTLET STRUCTURE B PROPOSED END SECTION PROPOSED UTILITY POLE

--- -- EASEMENT ---- WETLAND BUFFER . PROPOSED TREELINE PROPOSED BITUMINOUS CURB ----- PROPOSED SWALE

PROPERTY LINE

LANDSCAPE NOTES:

TO SHOW THE PROPOSED SITE LANDSCAPE WHICH PROVIDES CLIMATIC RELIEF AND AESTHETIC APPEAL.

2. STRIPPED TOPSOIL SHALL BE STOCKPILED AND REUSED ON THE SITE WHERE NEEDED. TOPSOIL SHALL BE A MINIMUM OF 4 INCHES DEEP (MEASURED WHEN CONSOLIDATED). TOPSOIL SHALL BE TREATED IF NEEDED TO PROMOTE HEALTHY GRASS WHEN SEEDED. SCARIFY AND REPEAT SEEDING AS NECESSARY.

3. SITE PREPARATION IS TO BE CONDUCTED WITH MINIMAL DISTURBANCE TO EXISTING VEGETATION WHICH WILL REMAIN. CONSTRUCTION MATERIALS, EQUIPMENT, VEHICLES OR TEMPORARY SOIL DEPOSITS SHALL NOT BE LOCATED WITHIN THE

DRIP-LINE OF TREES THAT ARE TO BE PRESERVED. 5. EXISTING TREES WHICH REMAIN SHALL BE PRUNED AND THINNED IF APPROPRIATE PER UNH COOPERATIVE EXTENSION

RECOMMENDATIONS TO MAINTAIN HEALTHY APPEARANCES. 6. ALL OPEN SPACE AREAS NOT COVERED WITH PLANTINGS SHALL BE COVERED WITH GRASS OR OTHER VEGETATIVE

GROUNDCOVERS, WITH THE EXCEPTION OF PLANTING BEDS WHICH MAY BE MULCHED. WHERE SLOPES OF 33% OR GREATER ARE CREATED OR DISTURBED, THEY SHALL BE COVERED OR PLANTED WITH DEEP ROOTED SPECIES TO PREVENT EROSION.

8. ALL DEAD, DYING, OR DISEASED VEGETATION SHALL BE PROMPTLY REPLACED, BASED ON SEASONAL PLANTING PRACTICES, WITH HEALTHY LIVING PLANTS IN ALL REQUIRED LANDSCAPE AREAS.

9. PROVIDE A MAINTENANCE ESCROW ACCOUNT TO ENSURE THAT ANY PLANTED MATERIALS WILL BE REPLACED IN THE

EVENT THEY ARE DAMAGED OR DIE WITHIN ONE YEAR AFTER FINAL COMPLETION OF THE PROJECT.

10. NO PLANTINGS SHALL CONFLICT WITH SNOW STORAGE AREAS, LIGHT FIXTURES AND UNDERGROUND UTILITIES. 11. NO LANDSCAPING CONFLICTS WITH SIGHT DISTANCE.

LANDSCAPE CALCULATION:


ONE TREE PER 60 FEET OF ACCESS WAY: 800 LF / 60 FT = 13.3 TREES

ONE TREE PER 20 PARKING SPACES: 24 SPACES / 20 SPACES = 1.2 TREES

14.5 = 15 TREES

PROJECT PLANT LIST

SYMBOL	QTY	BOTANICAL NAME	COMMON NAME	SIZE	HEIGHT	SPREAD
0	8	ACER RUBRUM "REDPOINTE"	RED MAPLE	12' B&B	30'-40'	30-40'
83	7	PRUNUS SEROTINA	BLACK CHERRY	12' B&B	40'-60'	30-40'
0	8	SYRINGA PATULA "MISS KIM"	MISS KIM LILAC	2'-2.5' B&E	8 8'-10'	6'-8'
	9	RHODODENDRON PRINOPHYLLUM	EARLY AZALEA	#7	6'-8"	4'-5'
#DL)	24	HEMEROCALLIS HYBRIDS	DAYLILY	#3	4'-8'	4'-8'



LANDSCAPE PLAN

JENNESSTOWN MANOR MAP 7, LOTS 39 & 39-1


> ROUTE 103 WARNER, NEW HAMPSHIRE MERRIMACK COUNTY

OWNER/APPLICANT:


PEACOCK HILL ROAD, LLC 145 OLD TOWN ROAD WEARE, NH 03281 BK. 3829 PG. 2512



Civil Engineering Land Surveying Landscape Architecture 10 Commerce Park North, Suite 3B, Bedford, NH 03110 Phone (603) 627-2881



		REVISION	NS .	
No.	DATE	DES	CRIPTION	BY
1	5/22/25	PER PB AND AC	OT COMMENTS	AEW
2	9/4/25	PER AOT COMME	ENTS	AEW
3	10/2/25	PER AOT COMME	ENTS	AEW
4	10/31/25	PER ARIES & FII	RE COMMENTS	JDL
5	11/18/25	PER AOT & CON	D. OF APPROVAL	AEW
DATI	E: MARCH 2	5, 2025	SCALE: 1" = 40'	
PRO.	JECT NO: 2	4-0307-1	SHEET 7 OF 16	



UTILITY NOTE

DIG SAFF

THE UNDERGROUND UTILITIES DEPICTED HEREON HAVE BEEN DRAWN FROM FIELD SURVEY INFORMATION AND OR PLOTTED FROM EXISTING DRAWINGS. KEACH-NORDSTROM ASSOCIATES, INC. MAKES NO GUARANTEES THAT THE UNDERGROUND UTILITIES DEPICTED COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. FURTHER, KEACH-NORDSTROM ASSOCIATES, INC. DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM THE INFORMATION AVAILABLE. KEACH-NORDSTROM ASSOCIATES, INC. HAS NOT PHYSICALLY LOCATED THE UNDERGROUND PORTIONS OF THE UTILITIES.

NPDES NOTE

THIS PROJECT DISTURBS IN EXCESS OF 1-ACRE OF LAND. THEREFORE IT WILL BE REQUIRED TO OBTAIN NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT COVERAGE AS ISSUED BY THE ENVIRONMENTAL PROTECTION AGENCY (EPA). THE OWNER/DEVELOPER AND "OPERATOR" (GENERAL CONTRACTOR) SHALL EACH BE REQUIRED TO PREPARE AND SUBMIT A NOTICE OF INTENT (NOI) TO THE EPA PRIOR TO THE START OF CONSTRUCTION AND SHALL BE RESPONSIBLE FOR THE PREPARATION AND IMPLEMENTATION OF A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) MEETING THE REQUIREMENTS OF THE CURRENT CONSTRUCTION GENERAL PERMIT.

LEGEND

☐ GB-F	GRANITE BOUND FOUND	\sim
O SP	STONE POST	
SB−F	STONE BOUND FOUND	
● DH-S	DRILL HOLE SET	
*	BENCHMARK	-
(D)	UTILITY POLE	
11	CATCH BASIN	
III .	PROPOSED CATCH BASIN	$-\infty$
	PROPOSED OUTLET STRUCTURE	
Α	PROPOSED END SECTION	
P	PROPOSED UTILITY POLE	177

TREELINE EDGE OF PAVEMENT EDGE OF GRAVEL --- EASEMENT

----- WETLAND --- WETLAND BUFFER PROPOSED TREELINE - - ABUTTER LINE

PROPOSED BITUMINOUS CURB - PROPERTY LINE


LIGHTING NOTES:

- 1. EXTERIOR LIGHTING SHALL BE DESIGNED TO COORDINATE WITH THE BUILDING ARCHITECTURE AND LANDSCAPING, AND SHOULD CONTRIBUTE TO THE CHARACTER OF THE PROPERTY, NEIGHBORHOOD, AND STREET.
- 2. THE STYLE OF LIGHTING FIXTURES USED SHALL BE UNIFORM FOR THE ENTIRE SITE.

 3. OUTDOOR LIGHTING IS RESTRICTED TO THAT WHICH IS NECESSARY FOR SAFETY AND SECURITY OF THE DEVELOPMENT.


 4. WHERE PRACTICAL, EXTERIOR LIGHTING INSTALLATIONS SHALL INCLUDE TIMERS, DIMMERS, MOTION SENSORS, OR PHOTOCELL CONTROLLERS THAT TURN THE LIGHTS OFF DURING DAYLIGHT HOURS OR HOURS WHEN LIGHTING IS NOT
- NEEDED ELIMINATE UNNEEDED LIGHTING. 5. EXTERIOR LIGHTING INSTALLATIONS SHALL BE DESIGNED TO AVOID HARSH CONTRASTS IN LIGHTING LEVELS.
- 6. THE PURPOSE OF THIS PLAN IS TO SHOW THE PROPOSED SITE LIGHTING.
 7. LIGHTING SHALL BE POSITIONED TO PREVENT UNDESIRABLE INCIDENTAL ILLUMINATION OF ABUTTING PROPERTIES, THE STREET, AND THE NIGHTTIME SKY.
- 8. SECURITY, [PARKING LOT, AND SIGN LIGHTING SHALL BE SHIELDED OR OTHERWISE DESIGN THE ENSURE THE LIGHT IS DIRECTED DOWNWARD.
- 9. TO PREVENT LIGHT POLLUTION AND IMPACTS ON ABUTTING PROPERTIES, THE TOTAL CUTOFF OF LIGHT SHOULD OCCUR WITHIN THE PROPERTY LINES OF THE LOT TO BE DEVELOPED.

Luminaire Schedule Qty Label Arrangement Description [MANUFAC] 28 Single 47356-016 EUROFASE



DECKARD, 12IN INTEGRATED LED OUTDOOR WALL LANTERN

NOT TO SCALE



LIGHTING PLAN

JENNESSTOWN MANOR MAP 7, LOTS 39 & 39-1

ROUTE 103 WARNER, NEW HAMPSHIRE MERRIMACK COUNTY


OWNER/APPLICANT:

PEACOCK HILL ROAD, LLC 145 OLD TOWN ROAD WEARE, NH 03281 BK. 3829 PG. 2512




KEACH-NORDSTROM ASSOCIATES, INC.


Civil Engineering Land Surveying Landscape Architecture 10 Commerce Park North, Suite 3B, Bedford, NH 03110 Phone (603) 627-2881



No.	DATE	DESCRIPTION	BY
1	5/22/25	PER PB AND AOT COMMENTS	AEW
2	9/4/25	PER AOT COMMENTS	AEW
3	10/2/25	PER AOT COMMENTS	AEW
4	10/31/25	PER ARIES & FIRE COMMENTS	JDL
5	11/18/25	PER AOT & COND. OF APPROVAL	AEW

DATE: MARCH 25, 2025 **SCALE:** 1'' = 40'PROJECT NO: 24-0307-1 SHEET 8 OF 16








UTILITY NOTE

THE UNDERGROUND UTILITIES DEPICTED HEREON HAVE BEEN DRAWN FROM FIELD SURVEY INFORMATION AND OR PLOTTED FROM EXISTING DRAWNGS. KEACH—NORDSTROM ASSOCIATES, INC. MAKES NO GUARANTEES THAT THE UNDERGROUND UTILITIES DEPICTED COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. FURTHER, KEACH—NORDSTROM ASSOCIATES, INC. DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM THE INFORMATION AVAILABLE. KEACH—NORDSTROM ASSOCIATES, INC. HAS NOT PHYSICALLY LOCATED THE UNDERGROUND PORTIONS OF THE UTILITIES.



DRIVEWAY PROFILE PLAN

JENNESSTOWN MANOR MAP 7, LOTS 39 & 39-1

ROUTE 103 WARNER, NEW HAMPSHIRE MERRIMACK COUNTY

OWNER/APPLICANT:


PEACOCK HILL ROAD, LLC 145 OLD TOWN ROAD WEARE, NH 03281 BK. 3829 PG. 2512



KEACH-NORDSTROM ASSOCIATES, INC.

Civil Engineering Land Surveying Landscape Architecture

10 Commerce Park North, Suite 3B, Bedford, NH 03110 Phone (603) 627-2881




No.	DATE	DESCRIPTION	BY
1	5/22/25	PER PB AND AOT COMMENTS	AEW
2	9/4/25	PER AOT COMMENTS	AEW
3	10/2/25	PER AOT COMMENTS	AEW
4	10/31/25	PER ARIES & FIRE COMMENTS	JDL
5	11/18/25	PER AOT & COND. OF APPROVAL	AEW


SHEET 11 OF 16


DRIVEWAY PROFILE

SCALE: 1" = 40'(HORIZ.)

1" = 4'(VERT.)









ALL CONCRETE TO BE 4000 PSI MIN.
 GALVANIZED STEEL GRATE TO BE BOLTED TO THE TOP OF THE STRUCTURE WITH 1/2" STAINLESS STEEL BOLTS AND THREADED INSERTS.

OUTLET CONTROL STRUCTURE #60P DETAIL
NOT TO SCALE






NOTES:

- CONSTRUCT THE LEVEL SPREADER LIP ON A ZERO PERCENT GRADE TO INSURE UNIFORM SPREADING OF RUN-OFF.
- GRADE TO INSURE UNIFORM SPREADING OF RUN-OFF.

 2. LEVEL SPREADER SHALL BE CONSTRUCTED ON UNDISTURBED SOIL AND NOT ON FILL.
- THE FLOW FROM THE LEVEL SPREADER SHALL OUTLET INTO STABILIZED AREAS. WATER SHOULD NOT RECONCENTRATE IMMEDIATELY BELOW THE SPREADER.
- PERIODIC INSPECTION AND REQUIRED MAINTENANCE SHALL BE PERFORMED.
- MAINTENANCE REQUIREMENTS:
- INSPECT AT LEAST ONCE ANNUALLY FOR ACCUMULATION OF SEDIMENT AND DEBRIS AND FOR SIGNS OF EROSION WITHIN APPROACH CHANNEL, SPREADER CHANNEL OR DOWN-SLOPE OF THE SPREADER.
- REMOVE DEBRIS WHENEVER OBSERVED DURING INSPECTION.
 REMOVE SEDIMENT WHEN ACCUMULATION EXCEEDS 25% OF
- SPREADER CHANNEL DEPTH.

 4. MOW AS REQUIRED BY LANDSCAPE DESIGN. AT A MINIMUM, MOW ANNUALLY TO CONTROL WOODY VEGETATION WITHIN THE
- SPREADER.
- SNOW SHOULD NOT BE STORED WITHIN OR DOWN-SLOPE OF THE LEVEL SPREADER OR ITS APPROACH CHANNEL.
- REPAIR ANY EROSION AND RE-GRADE OR REPLACE STONE
 BERM MATERIAL, AS WARRANTED BY INSPECTION.
- RECONSTRUCT THE SPREADER IF DOWN-SLOPE CHANNELIZATION INDICATES THAT THE SPREADER IS NOT LEVEL OR THAT DISCHARGE HAS BECOME CONCENTRATED, AND CORRECTIONS CANNOT BE MADE THROUGH MINOR

STONED BERMED LEVEL LIP SPREADER DETAIL NOT TO SCALE



PIPE OUTLET TO FLAT AREA WITH NO DEFINED CHANNEL NOT TO SCALE

(MARCH 2008)

	ELEVATION/DIMENSIONS				
LOCATION	LENGTH FT	W1 FT	W2 FT	d50 IN.	DEPTH IN.
OCKET POND 41P OUTLET	11	- 5	16	4	6
FILTRATION POND 21P OUTLET	13	5	18	5	8
OCKET POND 22P OUTLET	13	3	16	6	9
MH 211P OUTLET (HW #210)	14	5	19	3	6
	ALL LOCAT	IONS U	SE	6	9


PERCENT OF WEIGHT SMALLER THAN THE GIVEN SIZE	SIZE OF STONE	
100%	1.5 TO 2.0 d50	
85%	1.3 TO 1.8 d50	
50%	1.0 TO 1.5 d50	
15%	0.3 TO 0.5 d50	

CONSTRUCTION SPECIFICATIONS:

- THE SUBGRADE FOR THE FILTER MATERIAL, GEOTEXTILE FABRIC AND RIP RAP SHALL BE PREPARED TO THE LINES AND GRADES SHOWN ON THE PLANS.
- THE ROCK OR GRAVEL USED FOR FILTER OR RIP RAP SHALL CONFORM TO THE SPECIFIED GRADATION.
- 3. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE ROCK RIP RAP. DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12 INCHES.
- STONE FOR THE RIP RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.

MAINTENANCE

THE OUTLET PROTECTION SHOULD BE CHECKED AT LEAST ANNUALLY AND AFTER EVERY MAJOR RAIN EVENT. IF THE RIP RAP HAS BEEN DISPLACED, UNDERMINED, OR DAMAGED, IT SHOULD BE REPAIRED IMMEDIATELY. THE CHANNEL IMMEDIATELY BELOW THE OUTLET SHOULD BE CHECKED TO SEE THAT EROSION IS NOT OCCURRING. THE DOWNSTREAM CHANNEL SHOULD BE KEPT CLEAR OF OBSTRUCTIONS SUCH AS FALLEN TREES, DEBRIS, AND SEDIMENT THAT COULD CHANGE FLOW PATTERNS AND/OR TAILWATER DEPTHS ON THE PIPES. REPAIRS MUST BE CARRIED OUT IMMEDIATELY TO AVOID ADDITIONAL DAMAGE TO THE OUTLET PROTECTION APRON.




CONSTRUCTION DETAILS


JENNESSTOWN MANOR MAP 7, LOTS 39 & 39-1

> ROUTE 103 WARNER, NEW HAMPSHIRE MERRIMACK COUNTY

OWNER/APPLICANT:

PEACOCK HILL ROAD, LLC 145 OLD TOWN ROAD WEARE, NH 03281 BK. 3829 PG. 2512






		REVISIONS		
0.	DATE	DESCRIPTION	BY	
	5/22/25	PER PB AND AOT COMMENTS	AEW	
300	9/4/25	PER AOT COMMENTS	AEW	
. 4	10/2/25	PER AOT COMMENTS	AEW	
	10/31/25	PER ARIES & FIRE COMMENTS	JDL	
	11/18/25	PER AOT & COND. OF APPROVAL	AEW	
Œ.				

 DATE: MARCH 25, 2025
 SCALE: AS SHOWN

 PROJECT NO: 24-0307-1
 SHEET 14 OF 16



PLACE 4" OF FABRIC -

ALONG TRENCH AWAY

BACKFILL AND TAMP

FROM PROTECTED AREA

PERSPECTIVE VIEW

WOVEN WIRE FENCE

EMBED FILTER CLOTH

SILT FENCE DETAIL

NOT TO SCALE

(MARCH 2008)

MINIMUM 8" INTO GROUND

NON-WOVEN FILTER CLOTH -

6"x6"x14.5 GAGE

0.14 STAPLES

4'-0" (1.2m)

1. SLOPE SURFACE SHALL BE FREE OF ROCKS,

SHALL HAVE GOOD SOIL CONTACT.

BLANKETS.

CLODS, STICKS AND GRASS. MATS/ BLANKETS

2. APPLY PERMANENT SEEDING BEFORE PLACING

3. LAY BLANKETS LOOSELY AND STAKE OR STAPLE

TO MAINTAIN DIRECT CONTACT WITH THE SOIL. DO NOT STRETCH.

THREAD (E.G., POLYPROPYLENE) SHOULD NOT BE USED.

4. UTILIZE "WILDLIFE FRIENDLY" MATTING CONSISTING OF COCO OR JUTE, AND LACKING PLASTIC

MESH TO PROTECT SNAKES. WELDED PLASTIC OR "BIODEGRADABLE PLASTIC" NETTING OR

EROSION CONTROL BLANKETS - SLOPE INSTALLATION

NOT TO SCALE


MAINTENANCE:

MUD AND SOIL PARTICLES WILL EVENTUALLY CLOG THE VOIDS IN THE CRUSHED STONE AND THE EFFECTIVENESS OF THE CRUSHED STONE PAD WILL NOT BE SATISFACTORY. WHEN THIS OCCURS, THE PAD SHOULD BE TOPDRESSED WITH NEW CRUSHED STONE OR COMPLETE REPLACEMENT OF THE PAD MAY BE NECESSARY WHEN THE PAD BECOMES COMPLETELY

IF WASHING FACILITIES ARE USED, THE SEDIMENT TRAPS SHOULD BE CLEANED OUT AS OFTEN AS NECESSARY TO ASSURE THAT ADEQUATE TRAPPING EFFICIENCY AND STORAGE VOLUME IS AVAILABLE. VEGETATIVE FILTER STRIPS SHOULD BE MAINTAINED TO INSURE A VIGOROUS STAND OF VEGETATION AT ALL TIMES.

CONSTRUCTION SPECIFICATIONS:


- 1. STONE FOR A STABILIZED CONSTRUCTION EXIT SHALL BE 3 INCH STONE, RECLAIMED STONE OR RECYCLED CONCRETE EQUIVALENT.
- 2. THE MINIMUM LENGTH OF THE PAD SHALL BE 75 FEET, EXCEPT THAT THE MINIMUM LENGTH MAY BE REDUCED TO 50 FEET IS A 3-INCH TO 6-INCH HIGH BERM IS INSTALLED AT THE ENTRANCE OF THE PROJECT SITE.
- THE THICKNESS OF THE STONE FOR THE STABILIZED EXIT SHALL NOT BE LESS THAN 6
- 4. THE WIDTH OF THE EXIT SHALL NOT BE LESS THAN THE FULL WIDTH OF THE AREA WHERE INGRESS OR EGRESS OCCURS OR 10 FEET, WHICHEVER IS GREATER.
- 5. GEOTEXTILE FILTER CLOTH SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING THE STONE. FILTER CLOTH IS NOT REQUIRED FOR A SINGLE FAMILY RESIDENCE LOT.
- 6. ALL SURFACE WATER THAT IS FLOWING TO OR DIVERTED TOWARD THE CONSTRUCTION EXIT SHALL BE PIPED BENEATH THE EXIT. IF PIPING IS IMPRACTICAL, A BERM WITH 5:1 SLOPES THAT CAN BE CROSSED BY VEHICLES MAY BE SUBSTITUTED FOR THE PIPE.
- THE EXIT SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOPDRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, WASHED OR TRACKED ONTO PUBLIC RIGHT-OF-WAY MUST BE REMOVED PROMPTLY.
- WHEELS SHALL BE CLEANED TO REMOVE MUD PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-OF-WAY, WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING



PLAN VIEW

STABILIZED CONSTRUCTION EXIT DETAIL

NOT TO SCALE (APRIL 2018)



2"x2" WOODEN ----STAKE FILTREXX[®]SILTSOXX 3" TO 4" (12"-18" TYPICAL) OR -APPROVED EQUAL AREA TO BE PROTECTED WORK AREA

SECTION VIEW

1. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH

IF THE FABRIC ON A SILT FENCE SHOULD DECOMPOSE OR

SEDIMENT DEPOSITS SHOULD BE INSPECTED AFTER EVERY

STORM EVENT. THE DEPOSITS SHOULD BE REMOVED WHEN

SEDIMENT DEPOSITS THAT ARE REMOVED OR LEFT IN PLACE

AFTER THE FABRIC HAS BEEN REMOVED SHALL BE GRADED

TO CONFORM WITH THE EXISTING TOPOGRAPHY AND

VEGETATED.

THEY REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE

FENCE, THE FABRIC SHALL BE REPLACED PROMPTLY.

BECOME INEFFECTIVE DURING THE EXPECTED LIFE OF THE

RAINFALL. ANY REPAIRS THAT ARE REQUIRED SHALL BE MADE

RAINFALL AND AT LEAST DAILY DURING PROLONGED

36" MINIMUM

LENGTH 1-3/4"x1-3/4"

FENCE POST 10'-0'

O.C. MAXIMUM

UNDISTURBED

GROUND

SECTION

1. ALL MATERIAL TO MEET FILTREXX® SPECIFICATIONS.

- 2. SILTSOXX COMPOST/SOIL/ROCK/SEED FILL TO MEET APPLICATION REQUIREMENTS.
- 3. SILTSOXX DEPICTED IS FOR MINIMUM SLOPES. GREAT SLOPES
- MAY REQUIRE LARGER SOCKS PER THE ENGINEER.

NOT TO SCALE

4. COMPOST MATERIAL TO BE DISPERSED ON SITE, AS DETERMINED BY ENGINEER. FILTREXX® SILTSOXX® DETAIL

CONSTRUCTION SEQUENCE

BE IN PLACE AS SHOWN ON THE PROJECT PLANS.

- FIRST CUT AND CLEAR TREES AND BRUSH ONLY WITHIN DESIGNATED LIMITS OF CLEARING AS NECESSARY TO FACILITATE PROPOSED CONSTRUCTION. ALL TREES, BRANCHES AND OTHER VEGETATIVE MATERIALS SHALL BE PROPERLY DISPOSED OF OFF SITE BY THE CONTRACTOR. THIS PROJECT IS MANAGED TO MEET THE
- REQUIREMENTS AND INTENT OF RSA 430:53 AND AGR 3800 RELATIVE TO INVASIVE SPECIES. 2. PRIOR TO COMMENCEMENT OF ANY EARTHMOVING OPERATIONS, ALL APPLICABLE TEMPORARY EROSION CONTROL MEASURES, INCLUDING SPECIFIED PERIMETER SILTATION FENCING AND STABILIZED CONSTRUCTION EXIT SHALL
- COMPLETE GRUBBING OPERATIONS. ALL STUMPS AND SIMILAR ORGANIC DEBRIS SHALL BE PROPERLY DISPOSED OF BY THE CONTRACTOR. NATIVE ORGANIC SOIL MATERIALS SUITABLE FOR USE AS TOPSOIL SHALL BE STOCKPILED WITHIN AREAS OUT OF THE WAY OF OTHER CONSTRUCTIONS ACTIVITIES AND DRAINAGE FLOW. STOCKPILES SHALL BE TEMPORARILY SEEDED WITH WINTER RYE AND BE SURROUNDED WITH HAY BALES AND/OR FABRIC SILTATION FENCE IN ORDER TO PREVENT LOSS DUE TO EROSION.
- 4. BEGIN EARTHMOVING OPERATIONS, COMMENCING WITH WORK NEEDED TO BALANCE SITE AND FACILITATE BUILDING FOUNDATION AND RETAINING WALL CONSTRUCTION. PERMANENT DOWNSLOPE WORK SHALL BE PROTECTED FROM UPGRADIENT STORMWATER FLOW BY THE CONSTRUCTION OF TEMPORARY EARTHEN DIKES OR EXCAVATED SWALES.
- ONCE BUILDING FOUNDATION WORK IS UNDERWAY, CONTINUE EARTHMOVING OPERATIONS UNTIL DESIGN SUBGRADE IS ACHIEVED.
- 6. INSTALL DRAINAGE SWALE SYSTEMS AND OTHER UTILITIES WORKING FROM LOW TO HIGH. INCOMPLETE WORK SHALL BE PROTECTED FROM SILTATION BY THE USE OF SILTATION BARRIERS AROUND SWALES UNTIL THE SITE HAS
- BECOME FULLY STABILIZED. 7. PLACE GRAVEL AND CRUSHED GRAVEL OVER PROPOSED DRIVEWAY, WALKS AND PARKING AREAS AND COMPACT
- IN SPECIFIED LIFT THICKNESS. 8. COMPLETE EXCAVATION/STABILIZATION GRADING ACTIVITIES. WHEN COMPLETE, IMMEDIATELY BEGIN TOPSOILING
- PROPOSED TURF AREAS USING STOCKPILED LOAM SUPPLEMENTED WITH BORROW LOAM, IF NECESSARY, TO LEAVE A THICKNESS OF 4 INCHES OF FRIABLE LOAM.
- 9. FINE GRADE ALL FUTURE TURF AREAS AND HYDROSEED WITH THE SPECIFIED SEED MIXTURE IMMEDIATELY AFTER FINE GRADING IS COMPLETED. ALL AREAS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISH GRADE.
- INSTALL THE BINDER COURSE OF PAVEMENT OVER ALL DESIGNATED AREAS.
- 11. CONTINUE TO MONITOR AND RECTIFY MINOR SITE AND SLOPE EROSION UNTIL ENTIRE SITE APPEARS TO BE COMPLETELY STABILIZED AND VEGETATED WITH A HEALTHY STAND OF TURF OR GROUND COVER. MAINTAIN SPECIFIED SILTATION/EROSION CONTROL MEASURES THROUGH ONE WINTER.
- 12. INSTALL THE SPECIFIED WEARING COURSE OF PAVEMENT OVER THE BINDER COURSE 13. COMPLETE INSTALLATION OF LANDSCAPING, SIGNAGE AND OTHER SITE AMENITIES.

EROSION CONTROL NOTES

- 1. EXPOSED EARTHWORK SHALL BE CONFINED TO AS LIMITED AN AREA AS IS PRACTICAL AT ANY GIVEN TIME THROUGHOUT THE CONSTRUCTION SEQUENCE. AT NO TIME SHALL MORE THAN FIVE (5) ACRES OF SITE AREA BE IN AN UNSTABLE CONDITION. NO GIVEN AREA OF THE SITE SHALL BE LEFT IN AN UNSTABILIZED CONDITION FOR A PERIOD OF TIME EXCEEDING THIRTY (30) CALENDAR DAYS.
- TEMPORARY EROSION CONTROL MEASURES SHALL BE INSTALLED IN STRICT ACCORDANCE WITH PROJECT PLANS. IN ADDITION, SIMILAR MEASURES SHALL BE INSTALLED WHERE AND WHEN THE FIELD CONDITION, OR FIELD OPERATION OF THE INDIVIDUAL SITE CONTRACTOR, MAY WARRANT. ALL TEMPORARY EROSION CONTROL MEASURES USED SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER 0.25" OF RAINFALL OR MORE. THEY SHALL BE CLEANED AND MAINTAINED AND OTHERWISE KEPT IN AN EFFECTIVE OPERATING MANNER THROUGHOUT
- 3. ALL DISTURBED AREAS DESIGNATED TO BE TURF, SHALL RECEIVE A MINIMUM APPLICATION OF 4 INCHES OF LOAM (COMPACTED THICKNESS), PRIOR TO FINAL SEEDING AND MULCHING.
- ALL SWALES AND DITCHLINES SHALL BE PERIODICALLY CLEANED OF DEPOSITED SEDIMENT SO AS TO MAINTAIN AN EFFECTIVE GRADE AND CROSS SECTION. ALL SWALES AND DITCHLINES SHALL BE FULLY STABILIZED PRIOR TO HAVING STORMWATER DIRECTED TOWARDS THEM.
- 5. IN THE EVENT THAT, DURING CONSTRUCTION OF ANY PORTION OF THIS PROJECT, A WINTER SHUTDOWN IS NECESSARY, THE CONTRACTOR SHALL STABILIZE ALL INCOMPLETE WORK AND PROVIDE FOR SUITABLE METHODS
- OF DIVERTING RUNOFF IN ORDER TO ELIMINATE SHEET FLOW ACROSS FROZEN SURFACES. AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:
 - A. BASE COURSE GRAVELS ARE INSTALLED IN AREAS TO BE PAVED; B. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED;
 - A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP RAP HAS BEEN INSTALLED; OR
- D. EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED. 7. DUST SHALL BE CONTROLLED BY THE USE OF WATER AS NECESSARY THROUGHOUT THE CONSTRUCTION PERIOD, IN ACCORDANCE WITH ENV-A 1000.
- 8. IN NO WAY ARE THOSE TEMPORARY EROSION CONTROL MEASURES INDICATED ON THESE PLANS TO BE CONSIDERED ALL INCLUSIVE. THE CONTRACTOR SHALL USE JUDGEMENT IN INSTALLING SUPPLEMENTARY
- EROSION CONTROL MEASURES WHERE AND WHEN SPECIFIC SITE CONDITIONS AND/OR CONSTRUCTION 9. AREAS HAVING FINISH GRADE SLOPES OF 3:1 OR STEEPER, SHALL BE STABILIZED WITH JUTE MATTING WHEN AND IF FIELD CONDITIONS WARRANT, OR IF SO ORDERED. JUTE MATTING INSTALLED TO CONFORM WITH THE
- RECOMMENDED BEST MANAGEMENT PRACTICE OUTLINED IN VOLUME 3 OF THE NEW HAMPSHIRE STORMWATER MANUAL "EROSION AND SEDIMENT CONTROLS DURING CONSTRUCTION."
- 10. ALL DETENTION PONDS AND TREATMENT SWALES SHALL BE CONSTRUCTED PRIOR TO ANY EARTH MOVING ACTIVITIES THAT WILL INFLUENCE STORMWATER RUNOFF.
- 11. ALL ROADWAYS AND PARKING AREAS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.
- 12. ALL CUT AND FILL SLOPES SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.

WINTER CONSTRUCTION NOTES:

- ALL PROPOSED POST-DEVELOPMENT VEGETATED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 4:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE PLACEMENT OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT
- 2. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED WITH
- STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS. 3. AFTER OCTOBER 15TH, INCOMPLETE ROAD OR PARKING SURFACES SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL PER NHDOT ITEM 304.3 OR, IF
- CONSTRUCTION IS TO CONTINUE THROUGH THE WINTER SEASON, BE CLEARED OF ANY ACCUMULATED SNOW AFTER EACH STORM EVENT. 4. AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:
 - A. BASE COURSE GRAVELS ARE INSTALLED IN AREAS TO BE PAVED: B. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED;
 - C. A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP RAP HAS BEEN INSTALLED: OR
 - D. EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

CONSTRUCTION DETAILS

JENNESSTOWN MANOR MAP 7, LOTS 39 & 39-1 ROUTE 103


WARNER, NEW HAMPSHIRE MERRIMACK COUNTY

OWNER/APPLICANT:

PEACOCK HILL ROAD, LLC 145 OLD TOWN ROAD WEARE, NH 03281 BK. 3829 PG. 2512





Civil Engineering Land Surveying Landscape Architecture 10 Commerce Park North, Suite 3B, Bedford, NH 03110 Phone (603) 627-2881




No.	DATE	DESCRIPTION	BY
1	5/22/25	PER PB AND AOT COMMENTS	AEW
2	9/4/25	PER AOT COMMENTS	AEW
3	10/2/25	PER AOT COMMENTS	AEW
4	10/31/25	PER ARIES & FIRE COMMENTS	JDL
5	11/18/25	PER AOT & COND. OF APPROVAL	AEW

DATE: MARCH 25, 2025 SCALE: AS SHOWN PROJECT NO: 24-0307-1 SHEET 15 OF 16









REAR ELEVATION
SCALE: 1/8"=1'-0"

RESIDENTIAL DESIGN SOLUTIONS
BY LISA MELVIN, LLC
PO BOX 548 MONT VERNON, NH 03057
603-235-4246
LMELVIN548@GMAIL.COM

PREPARED FOR: 4 UNIT DWELLING

REVISIONS


ELEVATIONS

ATE: 1-26-2025

SCALE: AS NOTED DRAWN BY: LAM
JOB NO.: FIT-2501

A-1

© COPYRIGHT 2024 RESIDENTIAL DESIGN SOLUTIONS BY L.M.



0 Y VIN, LLC GMAIL 品 ENTIAL B SID OX

0

S

@

48

FOR: LLING REPARED F U 4

REVISIONS


OUNDATION

1-26-2025 SCALE: AS NOTED DRAWN BY: LAM

JOB NO .: FIT-2501

C COPYRIGHT 2024 RESIDENTIAL DESIGN

SOLUTIONS BY L.M.



1. 9-0" PLATE HEIGHT

03057 BY LISA MELVIN, LLC OX 548 MONT VERNON, N 603-235-4246 LMELVIN548@GMAIL.CC RESIDENTIAL BY LISA O BOX 548 MO

0


REVISIONS

MAIN FLOOR PLAN

1-26-2025 SCALE: AS NOTED DRAWN BY: LAM

JOB NO .: FIT-2501

A-3 © COPYRIGHT 2024 RESIDENTIAL DESIGN SOLUTIONS BY L.M.



8'-0" PLATE HEIGHT
 ALL EXTERIOR WINDOW HEADERS TO BE 2-2x0 UNLESS OTHERWISE NOTED

PREPARED FOR: 4 UNIT DWELLING

RESIDENTIAL I BY LISA O BOX 548 MOI


REVISIONS

110101

DATE: 1-26-2025
SCALE: AS NOTED
DRAWN BY: LAM
JOB NO.: FIT-2501

A-4

© COPYRIGHT 2024 RESIDENTIAL DESIGN SOLUTIONS BY L.M.






STAIR SECTION

SCALE: 1/4"=1'-0"

NOTE: SILLS OF ALL MINDOMS TO BE 24" ABOVE FLOOR (MIN.) IF THEY ARE HIGHER THAN 6'-0" ABOVE GRADE

MA	RK	QTY	R.O.	DESIGNATION	DESCRIPTION
A		8	36"x60"+/-		DOUBLE HUNG - EGRESS
В		17	72"×60"+/-		MULLED DOUBLE HUNG- EGRESS
(c		4	42"×42"+/-		DOUBLE CASEMENT
(Dt		4	48"×18"+/-		AMNING - TEMPERED
(E		4	30"x48"+/-		DOUBLE HUNG
(Ft	\rangle	1	30"×48"+/-		DOUBLE HUNG - TEMPERED
Gt	\rangle	1	48"x60"+/-	7 - H-318	FIXED - TEMPERED
(H	>	2	60"×60"+/-		MULLED DOUBLE HUNG

MARK	QTY	SIZE	DESCRIPTION
(1)	4	3068	GLAZED ENTRY
(2)	4	6068	SLIDER
(3)	4	16'x8'	OVERHEAD GARAGE DOOR
(4)	4	2868	B-LABEL W/ SELF CLOSING HINGES
(5)	16	2868	INTERIOR
(6)	28	2668	INTERIOR
(7)	4	2468	INTERIOR
8	8	5068	INTERIOR DOUBLE
(9)	4	4068	INTERIOR DOUBLE
(10)	4	2068	INTERIOR
(11)	4	1868	INTERIOR
(12)	4	3068	CASED OPENING



RNON, 548

3-235-4246 348@GMAIL

PREPARED FOR: 4 UNIT DWELLING

S

0

AND

SECTIONS

REVISIONS

1-26-2025 SCALE: AS NOTED DRAWN BY: LAM

JOB NO .: FIT-2501

RESIDENTIAL DESIGN SOLUTIONS BY L.M.